

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(MARQUETTE COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 46 N. R. 29 X. W.	#L-9
2. PROPERTY CONTROLLING IN SECTION 24	T. 46 N. R. 29 X. W.	#16
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 31, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner L-9 (1/4 corner between Sections 24 & 25, T46N, R29W):
 Spruce post (Not found. No subsequent monuments found.)
 Spruce 5 N62E 4 (Not found. No subsequent accessories found.)
 Spruce 5 S47W 15 (Not found. No subsequent accessories found.)

Corner 16 (East 1/16 corner between Sections 24 & 25, T46N, R29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner L-9: Restored on line between Section Corners 40.024 ch. to E and to W.
Corner 16: Established on line between Sec. Cor. 20.012 ch. E and 1/4 cor. 20.012 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner L-9: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Jack Pine 12 N36°W (mag.) 41.8 ft. "1/4S, NBT"
 Jack Pine 7 N50°E (mag.) 25.4 ft. "1/4S, NBT"
 Declination 2° 30' West.

Corner 16: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Jack Pine 15 N80°E (mag.) 29.7 ft. "1/16S, BT"
 Jack Pine 9 S81°W (mag.) 8.0 ft. "1/16S, BT"
 Declination 2° 15' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980

CHIEF OF SURVEY PARTY
Arthur O. Enger
 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

