

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(MARQUETTE COUNTY)

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 29 X W.	#K-7
2. PROPERTY CONTROLLING IN SECTION 13	T. 46 N. R. 29 X W.	#10
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K-7 (Section Corner 13, 14, 23, & 24, T46N, R29W):
 Cedar post (Not found. No subsequent monuments found.)
 Maple 10 N60W 27 (Not found. No subsequent accessories found.)
 Cedar 10 S E (Not found. No subsequent accessories found.)

Corner 10 (South 1/16 corner between Sections 13 & 14, T46N, R29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K-7: Restored 10-29-79 on line between 1/4 cor. 39.995 ch. N and 1/4 cor. 40.319 ch. S. This places it at the record distance of 14.55 ch. S of a stream mentioned in original field notes, and in close alignment with all the known or recovered section and quarter-section corners for a distance of 2 miles to the N and 2 miles to the S. It is unlikely that any corner in this 4 miles would have deviated greatly from the straight line between terminal corners, as would be the case if an E & W proportion were used to restore this corner by double proportionate measurements, said E & W measurements varying considerably from the record. **Corner 10:** Established 11-5-79 on line between Sec. Cor. 19.998 ch. S and 1/4 cor. 19.998 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner K-7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 White Pine 17 N 30°E (mag.) 27.9 ft. "S13, NBT"
 Cedar 7 N40°W (mag.) 31.0 ft. "S14, NBT"
 Declination 3° 00' West.

Corner 10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 White Pine 17 N22°W (mag.) 14.8 ft. "1/16S, BT"
 White Pine 22 S16°E (mag.) 31.4 ft. "1/16S, BT"
 Declination 2° 30' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

