

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(MARQUETTE COUNTY)

| FOR CORNERS OF --                           | LOCATED IN --  | CORNER CODE NUMBER |  |
|---|--|--------------------|--|
| 1. PUBLIC LAND SURVEY _____                 | T. 46 N. <input checked="" type="checkbox"/> R. 29 <input checked="" type="checkbox"/> | #K-9               | REGISTER OF DEEDS STAMP AND<br>FILING NUMBER |
| 2. PROPERTY CONTROLLING IN SECTION 24 _____ | T. 46 N. <input checked="" type="checkbox"/> R. 29 <input checked="" type="checkbox"/> | #15                |  |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____  | T. _____ N. _____ S. _____ R. _____ E. _____ W. _____                                  |                    |  |
| 4. LOT NO. _____, RECORDED PLAT _____       |  |                    |  |
| 5. PRIVATE CLAIMS _____                     |  |                    |  |

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner K-9 (Section Corner 23, 24, 25 & 26, T46N, R29W):
    - Cedar post (Not found. Found a later 3" x 3" x 42" cedar post).
    - Tamarack 16 S20W 14 (Probably found. No subsequent accessories found.)
    - Spruce 12 N49E 12 (Not found. No subsequent accessories found.)
  - Corner 15 (West 1/16 corner between Sections 24 & 25, T46N, R29W):
    - Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K-9: On 10-22-79 replaced the found cedar post, which was quite old, with new monument described below. Post appeared to have been set by unknown persons from the original tamarack BT, there being a rotted tamarack stump corresponding to same at the record bearing & distance from the post. Distances S and E to stream crossings agree with original record.

Corner 15: Established 11-1-79 on line between Sec. Cor. 20.012 ch. W and 1/4 cor. 20.012 ch. E.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner K-9: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
    - Tamarack 6 S21-1/2°E (mag.) 70.0 ft. "S24, NBT"
    - B. Spruce 6 N38° E (mag.) 17.0 ft. "S23, NBT"
    - Declination 1° 55' West.
  - Corner 15: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
    - White Pine 24 N83°W (mag.) 8.4 ft. "1/16S, BT"
    - Red Pine 12 S81°E (mag.) 28.9 ft. "1/16S, BT"
    - Declination 1° 25' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

