

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(MARQUETTE COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. 29 X. R. W.	#J-7
2. PROPERTY CONTROLLING IN SECTION 14	T. 46 N. 29 X. R. W.	#16
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 2, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner J-7 (1/4 corner between Sections 14 & 23, T46N, R29W):**
 Maple post (Not found. No subsequent monuments found.)
 Y. Birch 6 N72W 12 (Not found. No subsequent accessories found.)
 W. Pine 24 S62E 27 (Not found. No subsequent accessories found.)

Corner 16 (East 1/16 corner between Sections 14 & 23, T46N, R29W):
 Not established in original survey nor subsequently, apparently.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner J-7:** Restored on line between Section Corners 40.078 ch. to E and to W.
 There are many old white pine stumps in the vicinity of the corner, and possibly one of them is the remains of the original BT, but there was no way to prove exactly which one, in the absence of identifying marks and lack of consistency with record direction and distance from other known points.

Corner 16: Established on line between Sec. Cor. 20.039 ch. E and 1/4 cor. 20.039 ch. W.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner J-7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 8 S72°W (mag.) 18.0 ft. "1/4S, NBT"
 Red Maple 6 N 8°E (mag.) 14.2 ft. "1/4S, NBT"
 Declination 3° 15' West.

Corner 16: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Black Spruce 5 N83°W (mag.) 16.7 ft. "1/16S, BT"
 Black Spruce 5 N34°E (mag.) 6.8 ft. "1/16S, BT"
 Declination 2° 05' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 27, 1980

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

