

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(MARQUETTE COUNTY)

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. <del>K</del> R. 29 <del>K</del> W.	#J-9
2. PROPERTY CONTROLLING IN SECTION 23	T. 46 N. <del>K</del> R. 29 <del>K</del> W.	#15
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**Corner J-9 (1/4 corner between Sections 23 & 26, T46N, R29W):**  
 White pine post (Not found. No subsequent monuments found.)  
 W. Birch 5 N42E 24 (Not found. No subsequent accessories found.)  
 W. Birch 5 S61W 20 (Not found. No subsequent accessories found.)

**Corner 15 (West 1/16 corner between Sections 23 & 26, T46N, R29W):**  
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**Corner J-9:** Restored 11-6-79 proportionately on line between probable original line tree 12.119 ch. W and probable original section corner 39.930 ch. E.

**Corner 15:** Established 11-2-79 on line between Sec. Cor. 19.965 ch. W and 1/4 cor. 19.965 ch. E. Corner falls about 1.5 ft. off graded portion of a county road, on the west side.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Corner J-9:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 B. Spruce 5 S34°E (mag.) 17.3 ft. "1/4S, NBT"  
 Cedar 2 N79°E (mag.) 12.2 ft. "1/4S, NBT"  
 Cedar 5 N23°W (mag.) 4.4 ft. "1/4S, NBT"  
 Declination 2° 00' West.

**Corner 15:** ⊕ chiselled on a 12" x 12" x 18" (approx.) boulder.  
 Red Maple 11 N62-1/2°W (mag.) 49.2 ft. "1/16S, BT"  
 Red Maple 8 N31°E (mag.) 44.3 ft. "1/16S, BT"  
 Declination 1° 20' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

