

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(MARQUETTE COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. X. R. 29 W.	#I-10 & I-11
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 8, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner I-10 (1/4 corner between Sections 26 & 27, T46N, R29W):**
 W. Pine post (Not found. See B for subsequent monument.)
 Y. Pine 5 N15E 20 (Not found. No subsequent accessories found.)
 Y. Pine 7 N77W 10 (Not found. No subsequent accessories found.)
- Corner I-11 (Section Corner 26, 27, 34, & 35, T46N, R29W):**
 Maple post (Not found. No subsequent monuments found.)
 Y. Pine 18 S67W 42 (Not found. No subsequent accessories found.)
 W. Birch 6 N50E 33 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I-10: Restored proportionately on line between original Sec. Cor. 40.124 ch. N and original 1/4 cor. 80.248 ch. S. On 10-28-66, B. D. Buckler, R.L.S., placed on record a 12" J. Pine blazed on 4 sides and used as a rough single-wire fence corner, S57°24'E 13.8 ft. from corner as restored by the undersigned. As Buckler was not in possession of certain other corner and line information in order to check the blazed tree's location, he recorded it as found. I thought it more proper to restore the corner by proration, and did so.

Corner I-11: Restored proportionately on line between original corners 80.248 ch. to N and 40.124 ch. to S. Found a possible W. Pine 20 line tree stump bottom 9.30 ch. S on the true sec. line, which is almost proportional to the record distance of 9.24 ch.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner I-10:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Jack Pine 11 S40°E (mag.) 24.5 ft. "1/4S, NBT"
 Jack Pine 6 N49°E (mag.) 42.9 ft. "1/4S, NBT"
 Declination 3° 40' West.
- Corner I-11:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 White Birch 6 N65°W (mag.) 7.3 ft. "S27, NBT"
 Jack Pine 8 S20°E (mag.) 11.9 ft. "S35, NBT"
 Jack Pine 9 N51°E (mag.) 22.3 ft. "S26, NBT"
 Declination 1° 50' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

