

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(MARQUETTE COUNTY)

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 29 <input checked="" type="checkbox"/> W.	#K-11
2. PROPERTY CONTROLLING IN SECTION 25	T. 46 N. R. 29 <input checked="" type="checkbox"/> W.	#10
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K-11 (Section Corner 25, 26, 35, & 36, T46N, R29W):

- Spruce Pine post (Not found. Found iron pipe set by Buckler.)
- Spruce Pine 8 S28-1/2E 63 (Not found. No subsequent accessories found.)
- Spruce Pine 9 N60W 83 (Not found, No subsequent accessories found.)

Corner 10 (South 1/16 corner between Sections 25 & 26, T46N, R29W):

Not established in original survey. B. D. Buckler reports establishment of this corner on 10-13-66, but could find no monument. Did find his BT's.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K-11: Found iron pipe set by B. D. Buckler, R.L.S. #8887, on 10-13-66, but bent over and the description cap broken off; also, all of his NBT's had been cut down near ground level during logging operations. On 10-3-79 I replaced the damaged monument with a new one described below and made new witnesses. Buckler's record states, "This corner replaced 1.80 chains north of a large boulder as indicated in original notes. Found remains of jack pine stump bearing N60°W 83 links for one possible bearing tree. Found squared jack pine 6 links north of sec. cor. monument." Corner is also about 1 ch. S of summit of hill as per original record. **Corner 10:** Established 11-7-79 on line between Sec. Cor. 20.013 ch. S and 1/4 cor. 20.013 ch. N. By calculation from Buckler's BT data, his corner would have fallen N14°20'E 3.79 ft. from corner as established by undersigned.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner K-11: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Pine 12 N31-1/2°E (mag.) 27.5 ft. "S25, NBT"
 Red Pine 5 S65-1/2°E (mag.) 12.7 ft. "S36, NBT"
 Red Pine 9 S51-1/2°W (mag.) 31.6 ft. "S35, NBT"
 R. Maple 5 N49-1/2°W (mag.) 16.5 ft. "S26, NBT"
 Distances horizontal. Declination 0° 40' West.

Corner 10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Jack Pine 11 S70°W (mag.) 39.4 ft. "1/16S, BT"
 Jack Pine 8 S43°E (mag.) 19.2 ft. "1/16S, BT"
 Declination 2° 10' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

