

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(MARQUETTE COUNTY)

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 46 N. R. 29 X W.	#1-8
2. PROPERTY CONTROLLING IN SECTION 23	T. 46 N. R. 29 X W.	#3
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 6, 19 79, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner I-8 (1/4 corner between Sections 22 & 23, T46N, R29W):
 Sugar post (Not found. No subsequent monuments found.)
 W. Pine 22 N60W 39 (Possibly found. No subsequent accessories found.)
 Sugar 16 S54E 14 (Not found. No subsequent accessories found.)

Corner 3 (North 1/16 corner between Sections 22 & 23, T46N, R29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I-8: Restored proportionately on line between an original W. Pine 48 line tree stump 1.961 ch. N and an original Y. Pine 16 line tree stump 9.066 ch. S. The original record distances bet. the corner and each of these line trees was 1.96 ch. and 9.06 ch., respectively. Found the remains of a W. Pine stump N60°W from corner, which could have been the original W. Pine BT.

Corner 3: Established proportionately on line between original sec. cor. 19.9715 ch. N and original W. Pine 48 line tree 18.014 ch. S. The position is 19.9755 ch. N of the 1/4 cor. bet. Sec. 22 & 23.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner I-8: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Oak 4 S76°W (mag.) 17.8 ft. "1/4S, NBT"
 Red Oak 8 N26°E (mag.) 14.8 ft. "1/4S, NBT"
 Declination 1° 30' West.

Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 5 N75°E (mag.) 17.9 ft. "1/16S, BT"
 Red Maple 5 N40°W (mag.) 15.0 ft. "1/16S, BT"
 Declination 1° 10' West.

SIGNED BY _____ DATE _____

Carl R. Johnson

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson DATE March 7, 1980

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

