

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

(MARQUETTE COUNTY)

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 29 W. <input checked="" type="checkbox"/>	#I-6
2. PROPERTY CONTROL- ING IN SECTION 14	T. 46 N. R. 29 W. <input checked="" type="checkbox"/>	#3
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W. <input type="checkbox"/>	
4. LOT NO. _____, RECORDED PLAT		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 6, 19 79, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner I-6 (1/4 corner between Sections 14 & 15, T46N, R29W):**  
 Cedar post (Not found. No subsequent monuments found.)  
 Y. Birch 10 S73W 45 (Not found. No subsequent accessories found.)  
 Cedar 6 N77E 15 (Not found. No subsequent accessories found.)

**Corner 3 (North 1/16 corner between Sections 14 & 15, T46N, R29W):**  
 Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner I-6:** Restored on line between Sec. Cor. 40.641 ch. S and Sec. Cor. 40.158 ch. N. It is believed that in addition to a probable index error in the original measurement of this section line, a blunder was made between the measurement to a stream at 28.15 ch. and a ledge at 31.00 ch. My measurement was 28.17 ch. to the stream and 31.60 ch. to the ledge, indicating the probable dropping of a half-chain by the original surveyors. I therefore took this into account in my proration of the distance, thus the difference between the south half-mile and north half-mile.

**Corner 3:** Established on line between Sec. Cor. 20.079 ch. N and 1/4 cor. 20.079 ch. S.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner I-6:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 B. Spruce 12 N47°E (mag.) 6.5 ft. "1/4S, NBT"  
 B. Spruce 11 N59°W (mag.) 11.8 ft. "1/4S, NBT"  
 Declination 1° 10' West.

**Corner 3:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 B. Spruce 6 N61°W (mag.) 6.0 ft. "1/16S, BT"  
 B. Spruce 6 S30°E (mag.) 4.9 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

**Carl R. Johnson**  
 SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson DATE March 7 1980

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7 1980

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

