

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(MARQUETTE COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 29 <input checked="" type="checkbox"/> W.	#K-10
2. PROPERTY CONTROLLING IN SECTION <u>25</u>	T. 46 N. R. 29 <input checked="" type="checkbox"/> W.	#3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K-10 (1/4 corner between Sections 25 & 26, T46N, R29W):
 Cherry post (Not found. See B for subsequent monument.)
 Y. Pine 10 N81E 18 (Not found. See C for subsequent accessories).
 W. Birch 9 S41W 27 (Not found. See C for subsequent accessories).

Corner 3 (North 1/16 corner between Sections 25 & 26, T46N, R29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K-10: Restored 11-7-79 on line between Section Corners 40.0265 ch. to N and to S. Corner purportedly was restored at that position on 10-13-66 by B. D. Buckler, who placed a 3" x 3" x 4-1/2' squared & scribed cedar post for a monument. Subsequent remeasurement of this sec. line by the undersigned disclosed that Buckler's post was N15°W 5.0 ft. from the true midpoint location as intended. I moved the corner to the position he intended to occupy and installed a new monument described below.
Corner 3: Established 11-1-79 on line between Sec. Cor. 20.013 ch. N and 1/4 cor. 20.013 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner K-10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 White Spruce 14 S36°W (mag.) 10.7 ft. "1/4S, NBT"
 Red Pine 22 N13°E (mag.) 109.0 ft. "1/4S, NBT"
 Note: These are same trees as marked by Buckler. Declination 1° 45' West.
Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Cedar 6 N37-1/2°E (mag.) 19.0 ft. "1/16S, BT"
 Cedar 5 S78-1/2°E (mag.) 23.5 ft. "1/16S, BT"
 Declination 2° 00' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE March 7, 1980
 MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

