

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(MARQUETTE COUNTY)

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 46 N. R. 29 X W.	#M-1 & M-2
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 6, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner M-1 (Section Corner 1, 6, 31 & 36, T46-47N, R28-29W):
 Found a 2" I.D. x 66" iron pipe alongside a 3" x 3" x 24" squared cedar post at an old fence corner. Found no subsequent accessories.

Corner M-2 (1/4 corner bet. Sec. 1 & 6, T46N, R28-29W):
 Fir post (Not found. No subsequent monuments found.)
 Tamarack 20 N20E 104 (Not found. No subsequent accessories found.)
 Fir 6 N21W 56 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner M-1: History of corner unknown, but is supported by measurements to original line tree 66.70 ch. S (record: 66.64 ch.) and to stream 3.10 ch. W (record: 3.20 ch.).
Corner M-2: Restored proportionately on line between W. Pine 50 line tree 27.313 ch. S and Twp. Cor. 39.484 ch. N. Corner falls in beaver marsh, about 1/2 ch. N of a stream running W'ly, as mentioned in original field notes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner M-1: Replaced found pipe with 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Jack Pine 11 N27°W (mag.) 42.5 ft. "S36, NBT"
 Jack Pine 11 S58°E (mag.) 73.9 ft. "S 6, NBT"
 J. Pine 13 N22°E (mag.) 29.9 ft. "S31, NBT"
 Declination 1° 05' West.
Corner M-2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Corner in beaver-flooded marsh, no suitable witness trees within reasonable distance.
 Declination 2° 25' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 9, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources
 13581

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

