

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(MARQUETTE COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 29 X. W.	#M-3
2. PROPERTY CONTROLLING IN SECTION 12	T. 46 N. R. 29 X. W.	#7
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 17, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner M-3 (Section Corner 1, 6, 7, & 12, T46N, R28-29W):
 Cedar post (Not found. No subsequent monuments found.)
 Spruce 7 S11E 18 (Not found. No subsequent accessories found.)
 Cedar 8 N22W 11 (Not found. No subsequent accessories found.)

Corner 7 (North 1/16 corner between Sections 7 & 12, T46N, R28-29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner M-3: Restored proportionately on line between an original corner 40.086 ch. S and an original line tree 12.850 ch. N. Found a badly rotted cedar stump to NW of corner, which could have been an original BT.

Corner 7: Established on line between Sec. Cor. 20.043 ch. N and 1/4 cor. 20.043 ch. S. Corner is in a marsh bordering a stream about 2 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M-3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 White Pine 24 S64-1/2°E (mag.) 33.8 ft. "S 7, NBT"
 White Pine 12 S 10°W (mag.) 28.0 ft. "S12, NBT"
 Declination 2° 25' West.

Corner 7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 White Pine 20 S 7-1/2°W (mag.) 103.9 ft. "1/16S, BT"
 White Pine 26 S56°E (mag.) 88.7 ft. "1/16S, BT"
 Declination 2° 35' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

