

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --	(MARQUETTE COUNTY) LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 29 <input checked="" type="checkbox"/> W.	#M-4
2. PROPERTY CONTROLLING IN SECTION	12, T. 46 N. R. 29 <input checked="" type="checkbox"/> W.	#14
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner M-4 (1/4 corner between Sections 7 & 12, T46N, R28-29W):
 Spruce post (Not found. No subsequent monuments found.)
 W. Birch 5 N68E 18 (Not found. No subsequent accessories found.)
 W. Pine 30 S12W 18 (Probably found. No subsequent accessories found.)

Corner 14 (South 1/16 corner between Sections 7 & 12, T46N, R28-29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner M-4: Restored 10-5-79 from remains of probable W. Pine BT, identified from overgrowth scar tissue with possible remnant axe mark on a fragment of its wood, and confirmed by its location with reference to a granite outcrop 14 chains S in a swamp, which is very distinctive and unmistakable as the outcrop referred to in the original field notes. Corner also falls on the W end of a granite knob as reported in original field notes.
Corner 14: Established 10-18-79 on line between 1/4 cor. 20.035 ch. N and Sec. Cor. 20.035 ch. S. Corner is in a large spruce-tamarack bog swamp.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M-4: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 White Pine 11 N39°E (mag.) 13.2 ft. "1/4S, NBT"
 Red Pine 14 S46-1/2°E (mag.) 13.3 ft. "1/4S, NBT"
 Declination 1° 35' West.
Corner 14: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Tamarack 3 S27°W (mag.) 15.5 ft. "1/16S, BT"
 Tamarack 3 S27°E (mag.) 20.7 ft. "1/16S, BT"
 Declination is 1° 45' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

