

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(MARQUETTE COUNTY)

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. 29 X. R. W.	#M-5
2. PROPERTY CONTROLLING IN SECTION 13	T. 46 N. 29 X. R. W.	#2
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner M-5 (Section Corner 7, 12, 13, & 18, T46N, R28-29W):
 Spruce post (Not found. See B for subsequent monument.)
 Tamarack 8 S78W 45 (Not found. No subsequent accessories found.)
 Spruce 6 N73E 23 (Not found. No subsequent accessories found.)

Corner 2 (East 1/16 corner between Sections 12 & 13, T46N, R29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner M-5: On 10-8-79, restored corner proportionately on line between Sec. Cor. 240.416 ch. S and an original 1/4 cor. 40.069 ch. N. Position checks closely with original field note calls to a granite outcrop in swamp 26 ch. N and with original Sec. Cor. 80.477 ch. W. Found 2 wood posts, of apparently different ages but no more than 20-30 years old, S63°40.6'W 179.14 ft., apparently set by foresters or timber cruisers for an approx. corner.

Corner 2: Established 11-2-79 on line between 1/4 cor. 20.119 ch. W and Sec. Cor. 20.119 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M-5: 1" I.D. x 48" iron pipe with 4" brass cap.
 Tamarack 3 N37°W (mag.) 52.0 ft. "S12, NBT"
 Tamarack 3 S 7°E (mag.) 36.9 ft. "S18, NBT"
 Cedar 10 N53°E (mag.) 18.0 ft. "S 7, NBT"
 Declination 1° 20' West.

Corner 2: ⊕ chiselled in bedrock, with a 1" I.D. x 18" iron pipe with 3 3/4" aluminum cap set in a mound of rocks over it.
 B. Spruce 6 N78°E (mag.) 5.5 ft. "1/16S, BT"
 W. Pine 13 S25°E (mag.) 2.3 ft. "1/16S, BT"
 Declination 1° 45' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

