

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	(MARQUETTE COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 29 X W.	#M-7 & M-8
2. PROPERTY CONTROLLING IN SECTION	24 T. 46 N. R. 29 X W.	#7
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner M-7 (Section Corner 13, 18, 19 & 24, T46N, R28-29W):
 - Cedar post (Not found. No subsequent monuments found.)
 - Y. Birch 14 S38E 28' (Not found. No subsequent accessories found.)
 - Spruce 8 N45W 6' (Not found. No subsequent accessories found.)
 - Corner M-8 (1/4 corner between Sections 19 & 24, T46N, R28-29W):
 - Cedar post (Not found. See B for subsequent monument.)
 - Tamarack 5 S13E 6' (Not found. No subsequent accessories found.)
 - Tamarack 8 N34W 22' (Not found. No subsequent accessories found.)
 - Corner 7 (North 1/16 corner between Sections 19 & 24, T46N, R28-29W):
 - Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner M-7: Restored 10-9-79 proportionately on line between Sec. Cor. 160.227 ch. S and an original 1/4 cor. 120.208 ch. N. Corner appears to fall about .5 ch. N of swamp edge, rather than 1 ch. S of it as given in original field notes, but 135 years ago the transition zone bet. swamp and upland may have looked differently than it does today. Corner M-8: Restored 10-9-79 proportionately on line between Sec. Cor. 120.208 ch. S and original 1/4 cor. 160.277 ch. N. There is an old fence corner S73°24.2'W 30.43 ft., but nothing apparently supports it as being at the original corner position. Corner 7: Established 10-19-79 on line between 1/4 cor. 20.035 ch. S and Sec. Cor. 20.035 ch. N.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Monuments for all 3 corners: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
- Witnesses for Corner M-7: Cedar 8 S33-1/2°E (mag.) 48.2 ft. "S19, NBT"
 - Declination 1° 40' West. Cedar 8 S56-1/2°W (mag.) 33.7 ft. "S24, NBT"
 - Witnesses for Corner M-8: Cedar 9 N20°W (mag.) 19.0 ft. "1/4S, NBT"
 - Declination 1° 40' West. Cedar 7 N55°E (mag.) 19.6 ft. "1/4S, NBT"
 - Witnesses for Corner 7: Red Maple 12 S42°W (mag.) 30.8 ft. "1/16S, BT"
 - Declination 1° 55' West. Red Maple 5 N24°E (mag.) 11.5 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1988

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

