

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

| FOR CORNERS OF— | LOCATED IN— | CORNER CODE NUMBER | |
|---|--------------------------------|--------------------|--|
| 1. PUBLIC LAND SURVEY _____ | T. 46 N. R. 29 X W. | #M-9 | REGISTER OF DEEDS STAMP AND FILING NUMBER |
| 2. PROPERTY CONTROLLING IN SECTION 24 _____ | T. 46 N. R. 29 X W. | #14 | |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. S. R. _____ E. W. | | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | | |
| 5. PRIVATE CLAIMS _____ | | | |

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner M-9 (Section Corner 19, 24, 25 & 30, T46N, R28-29W):
 Spruce 4 for corner (Not found. No subsequent monuments found.)
 Spruce 4 S31W 10 (Not found. No subsequent accessories found.)
 Spruce 4 N31E 11 (Not found. No subsequent accessories found.)

Corner 14 (Witness Corner for South 1/16 corner between Sections 19 & 24, T46N, R28-29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner M-9: Restored 10-9-79 proportionately on line between Sec. Cor. 80.139 ch. S and original 1/4 cor. 200.347 ch. N. Corner in spruce swamp; leave swamp about 1 ch. E, as per original field notes.
Corner 14: On 10-31-79, placed a witness monument N0°09.3'E 22.0 ft. from position of true 1/16 cor., which falls on the North approach abutment of a crude wood bridge over a beaver-flooded stream. True cor. would have been established on line between Sec. Cor. 20.035 ch. S and 1/4 cor. 20.035 ch. N; witness monument is established on line between Sec. Cor. 20.368 ch. S and 1/4 cor. 19.702 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M-9: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 White Pine 16 S74°E (mag.) 25.9 ft. "S30, NBT"
 White Pine 16 N29°W (mag.) 43.4 ft. "S24, NBT"
 Declination 1° 50' West.

Corner 14: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap for Witness Corner.
 No trees or other suitable "permanent" bearing objects conveniently available.
 Declination 0° 50' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

