

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MARQUETTE COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46N. ^{N.} X. R. 29 ^{W.}	G7
2. PROPERTY CONTROLLING IN SECTION 22	T. 46N. ^{N.} X. R. 29 ^{W.}	5, Meander corner between 1 and 4
3. MISCELLANEOUS PROPERTY IN SECTION	T. ^{N.} S. R. ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G7: Found 1 1/2" I.D. Iron Pipe set by unknown person from original bearing trees.

Meander corner: Not set on original survey nor subsequently apparently.

Corner 5: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G7: Restored 6-30-82 at Iron Pipe.

Meander corner: Established 6-30-82 during section subdivision.

Corner 5: Established 7-7-82 during section subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G7: 1 1/2" I.D. by unknown length Iron Pipe.
4" Maple N75W 18.5 ft S16, NBT
W. Pine N86E 14.8 ft. S15, NBT
4" Maple S07W 21.7 ft. S21, NBT

Meander corner: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap.
10" Red pine N32E 14.2 ft MC, BT
10" Red pine S75W 10.7 ft. MC, BT
10" Red pine S54E 15.5 ft. MC, BT
10" Red pine south 1.5 ft. squared

Corner 5: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap
6" Maple S70E 36.9 ft. 1/16S, BT
4" Maple S34W 38.9 ft. 1/16S, BT
8" W. Birch N88W 39.4 ft. 1/16S, BT

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-83

CHIEF OF SURVEY PARTY
Keith L. Sackett
MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006