

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MARQUETTE COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 29 X. W.	G 8 J 6
2. PROPERTY CONTROLLING IN SECTION	22 T. 46 N. R. 29 X. W.	Meander corner between 4 and 5
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett on _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G8: Original monument and accessories not found. Found one possible original bearing tree (cedar 5" S40W 11.22 ft) tree is down and dead.

Corner J6: Not set on original survey nor subsequently apparently. Found old axle shaft 117 ft. S68°W.

Meander corner: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G8: Restored 6-29-82 midway and on line between section corners north and south. This location checks with possible original bearing tree and swamp edge north.

Corner J6: Established 6-11-82 at the intersection of N-S-E-W 1/4 lines.

Meander corner: Established 7-7-82 during section subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G8: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap.

7" cedar N10E 9.5 ft. 1/4S, NBT

5" cedar N82E 6.7 ft. 1/4S, NBT

4" cedar N25W 16.4 ft. 1/4S, NBT

Corner J6: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap.

6" Spruce S37E 6.5 ft. 1/16S, BT

16" W. pine N19E 10.1 ft. 1/16S, BT

4" Spruce N13W 4.1 ft 1/16S, BT

Meander Corner: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap.

12" W. pine N40W 6.5 ft. MC, BT

10" R. Pine N43E 18.8 ft. MC, BT

15" R. Pine S07E 16.2 ft. MC, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 7-6-83

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

