

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette
(County)

Located In:

Corner Code #

1. Public Land Survey	T 46N R 29W	K10
	T 46N R 29W	J9
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Aug 06 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
(K10) Quarter corner common to Sections 25-26. 1983: Recorded by D.E.Erickson, LLS in Liber 4, Page 33, Marquette Co. records.
(J9) Quarter corner between Sections 23-26. 1979: Restored by A.O.Enger: "proportionately on line between probable original line tree 12.119 ch. W and probable original section corner 39.930 ch. E." Set 1"IDx36" I.pipe with 3 3/4" alum. cap. 8.Spruce 5 S34E 17.3', Cedar 2 N79E 12.2', Cedar 5 N23W 4.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K10) Recovered the 1979 MDNR monument noted in the 1983 record, in good condition, and at substantial record bearing and distance from the 1983 witnesses. The Spruce N06W has been cut down. The remaining witnesses are in good condition with overgrown blazes. Left the monument in place and made one new witness as described below.

(J9) Recovered the 1979 monument in good condition and at record bearing and distance from the 1979 witnesses. The 8.Spruce SE is dead and down. The cedars are in good condition with partially overgrown to overgrown blazes and were found marked with a measuring nail and surveyor's tag #17618. I reviewed the notes of Enger's 1979 survey and determined that he restored this corner at the proper proportional position between the noted line tree and section corner. However, he misstated the distance on the 1979 LCRC to the section corner, which should have been properly reported as 40.129 chains east. I found it to be 40.108 chains east. I accept the monument at J9 as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K10) Found 1"ID I.pipe with 4" alum. MDNR cap. Blazed, scribed and set measuring nail in:

4" Balsam N02W 27.4' "1/4S NBT"
Remeasured the 1983 witnesses:
7" Balsam N54E 8.2' to nail in side
5" Balsam S44E 5.6' do
16" Spruce S41W 11.2' do

Bearings are magnetic. Distances are to nail with tag. Set sq'd cedar post adjacent.

Signed by Stephan J. Szyszkoski

Surveyor's Michigan License No. 33986

(J9) Found 1"ID I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:

6" 8.Spruce S51W 25.6' "1/4S N8T"
3" W.Spruce S70E 21.4' do
Existing witnesses:
5" Cedar N83E 12.1' found tag #17618
8" Cedar N18W 4.35' do

Fd. sq'd and scribed cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.

Date 9/3/03

