

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Marquette

(County)

Located In:

Corner Code #

1. Public Land Survey	T 46N R 29W	J13
	T 46N R 29W	K12
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Aug 27 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 (J13) Quarter corner common to Section 35 T46N-R29W and Section 2 T45N-R29W. 1959: Remonumented by Billy D. Buckler RLS from BT evidence. Set 1" pipe with 4" brass cap. 12" J.Pine S84E 164 links, 9" Aspen S22E 9 links.  
 (K12) Quarter corner common to Sections 35-36. 1983: David E. Erickson, RLS 29245 reestablished this corner by proportionate measurement between Section corners. Set 5/8"x36" rebar with plastic cap marked "D.Erickson L.S. No. 29245" witnessed by 6" spikes and washers in: 9" W.Birch N9E 30.64', 11" R.Pine S63E 47.22', 20" J.Pine S22W 33.74', 12" Oak S80W 15.31'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J13) Recovered the 1959 monument in good condition and at record bearing and distance from the 1959 witnesses. The J.Pine is now dead but standing, the Aspen is a rotting stump. Left the monument in place and made new witnesses as described below.  
 (K12) Recovered the monument in good condition, as described, and at substantial record bearing and distance from the 1983 witnesses. The 9" W.Birch is now dead. The others are in good condition with old blazes visible. The position of the monument is in reasonable accord with the above record, being within 0.6' of the intended position. Accepted the monument as a careful and faithful reestablishment of the position of the original corner. Made one new witness as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J13) Found 1" ID I.pipe with 4" brass State of Michigan cap. Blazed, scribed, and set measuring nails in: 3" Oak N36E 14.3'      1/4S NBT" 3" J.Pine S58W 48.1'      do 7" R.Pine S33W 46.4'      do 4" Maple S03E 63.4'      do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(K12) Found 5/8" rebar with plastic cap #29245. Set measuring nail/tag in: 3" Oak N65E 11.7' The 1983 wits: 14" R.Pine S63E 40.7'      spike/tag 17" J.Pine S24W 33.9'      do 14" Oak S83W 15.3'      do Bearings are magnetic. Distances are to nails with tag. Sq'd cedar post adjacent.
---	---



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 9/3/03