

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Marquette

(County)

Located In:

Corner Code #

1. Public Land Survey

T 46N R 29W

I11

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Aug 27 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(I11) Corner common to Sections 26-27-34-35. 1979: A.O.Enger RLS restored the corner by proportionate measurement between original corners 80.248 ch. W and 40.124 ch. S. Set 1"IDx36" I.pipe with 3 3/4" alum. cap. W.Birch 6 N65W 7.3', J.Pine 8 S20E 11.9', J.Pine 9 N51E 22.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I11) Recovered the 1979 monument in good condition and at record bearing and distance from the 1979 witnesses. The J.Pine NE is now dead and down. The W.Birch was removed during this survey to facilitate GPS observations. The position of the monument is in reasonable accord with the record above, being 1.05' from the intended position. I accept the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I11) Found 1"ID I.pipe with 4" alum.

MDNR cap. Blazed, scribed, and set

measuring nails in:

9" J.Pine S23E 12.4' \* "S35 NBT"

8" J.Pine N52W 3.1' "S27 NBT"

9" J.Pine N02W 56.0' "S27 NBT"

7" J.Pine S53E 15.9' "S35 NBT"

Bearings are magnetic. Distances are to

nail with tag. Set sq'd cedar post

adjacent. \* denotes the 1979 NBT

Signed by Stephan J. Szyszkoski

Date 9/3/03

Surveyor's Michigan License No. 33986

