

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> N. S., R. <u>23</u> E. W.	<u>K-4, L-3, M-3</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on March 18 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- K-4 West  $\frac{1}{4}$  corner - Section 12; Wood Post, Spruce 10" - N45°E - 13 lks.; Do 9" - S60°W - 25 lks
- L-3 North  $\frac{1}{4}$  Corner - Section 12; Wood Post, Y. Pine 9" - N2°W - 17 lks; Do 14" - S50°E - 32 lks
- M-3 N.E. Section Corner - Section 12; From Marquette County Road Commission; iron pin with brass cap at fork of roads. Old original Pine B.T. N46°W 31.9' in good condition. Set new B.T.'s N. Pine 12" - N30°E - 16.0'; N. Pine 10" - S23°W - 26.2'.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- K-4 Found 3"x3" sq. stake & several old stake points beside it. M.D.S.H. witnesses from state highway M-28 survey are in place as shown on highway plans. Very definite line tree on line south.
- L-3 Found 1 $\frac{1}{2}$ " pipe with two old N.B.T.'s - blazed but not scribed - not of record but fits the location of section corners  $\frac{1}{2}$  mile east &  $\frac{1}{2}$  mile west reasonably well.
- M-3 Found 1" pipe with brass plug and both county N.B.T.'s in place as recorded except the N.E. one is N45°E instead of N30°E as their record shows. Scribing is plain on both N.B.T.'s. No sign of original B.T.'s at this time.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner**

- K-4 1" pipe, 4" aluminum cap; 3" Tamarack - N49°W - 69.7'; 3" Spruce - N41°W - 3.5'; 3" Spruce, S36°W - 21.5'; 3" R. Pine - S32°E - 13.2'; 3" Spruce - S40°E - 4.6'; 6" Tamarack - S26°W - 125.0'.
- L-3 Found 1 $\frac{1}{2}$ " pipe; 13" R. Pine - N60°W - 27.4'; 6" R. Pine - S89°E - 24.5'; 13" R. Pine - S6°E - 18.5'; 13" R. Pine - S31°W - 12.95'.
- M-3 1" iron pipe with brass plug; 13" R. Pine - S23°W - 26.40' (old Co. Rd. Comm. N.B.T. ); 12" R. Pine - N45°E - 16.43' (old Co. Rd. Comm. N.B.T. ); 9" R. Pine - N28°W - 15.84'; 7" R. Pine - S19°E - 34.35'; 9" R. Pine - S38°E - 25.11'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt DATE 3-19-80  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558