

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>47</u> <sup>N</sup> / <sub>S</sub> , R. <u>23</u> <sup>E</sup> / <sub>W</sub> .		<u>K-8, K-9</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____, E., W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____, E., W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 2 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

<p><b>K-8 Woodpost:</b></p> <p>Hemlock 11 N86°W 31 links          Cedar 7 N66°E 14 links</p> <p>Subsequent monument:          Woodpost</p>	<p><b>K-9 Woodpost:</b></p> <p>Hemlock 14 N42°W 25 links          Hemlock 14 S30°W 20 links</p>
--	---

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-8 This corner was replaced from an original B.T. (Hemlock 11, N86°W 31 links). Now a rotted stump overgrowth of lower face found in the earth at base of stump. Down woodpost at corner.

K-9 This corner was replaced from one B.T., a fallen stub with scribe marks on upper face and overgrowth of lower face. Rotted stump in proper position for the second B.T. Trace of post found in soil at proper location. Notes state bearing N42°W for one B.T. This B.T. had section 24 scribed on it and from the position in its fallen state, and the other evidence found, would make the bearing N42°E, 25 links.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Corner monument: woodpost K-9 1" iron pipe with 4" brass cap. Bearings-magnetic.

K-8	10" Cedar (1/8)	(NBT)	N40°E	19.4'
	12" Cedar (1/8)	(NBT)	S23°W	15.6'
K-9	12" Cedar (S26)	(NBT)	S48°W	39.6'
	7" Spruce (S25)	(NBT)	S50°WE	15.0'

*K-8 1" iron pipe with 4" Alum. cap.*

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Frank J. Bray CHIEF OF SURVEY PARTY DATE 11-1-73  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575