

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> N. S., R. <u>23</u> E. W.	<u>K-3</u> <u>K 5</u> <u>4-11-79</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on December 6 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

K-3 (S.W) section corner - Section 12; Wood Post - in edge of swamp; Cedar 10 - N34°E - 13 lks.; Hemlock 9 - S52½°W - 9 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

K-3 Set from remains of Hem. stump S52½°W-5.9' and remains of Cedar stump N34°E-8.6' for original bearing trees. Both badly burned and rotted no identifying marks left, however the stream call 7.51 chs. east fits well and it is about 2' north of a prop. position for 2 miles N & S and a positively identified line tree recorded as "30.25 - Y. Pine 8 on small dry spot" falls 1.3' east of a line between this corner and a sq. Cedar stake found in place for the West ¼ corner of Sec. 12 at 1980.5' (30.01 chs.) north of this corner. Also, a very old dead & down Cedar with north & south line blazes falls on line about 200' north of this corner. This corner also falls in the edge of swamp as described in the G.L.O. record.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-3 1" pipe, 4" aluminum cap; 12" W. Birch - S58°W - 48.8'; 15" W. Birch - S2°W - 7.3'; 9" W. Birch - N65°W - 39.3'; 7" Maple - N1°E - 45.0'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 3-12-80  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558