

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 47 N. S., R. 23 E. W.	M-4
2. PROPERTY CONTROLLING IN SECTION 12	T. 47 N. S., R. 23 E. W.	3, 5
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 19 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- M-4 East 1/4 corner - Section 12; Original notes say "1/4 section corner in lake".
- 3 North 1/16 corner on west section line - Section 12; not previously established.
- 5 North 1/16 corner on the N-S 1/4 line of Section 12; not previously established.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- M-4 Set M.P.O.L. between the NE and SE section corners of Sec. 12. Falls in what once was lake bottom before the road was built. Measure to edge of lake south is okay - lakeshore north is not definite.
- 3 Set M.P.O.L. between the W 1/4 corner and the NW section corner of Section 12.
- 5 Set M.P.O.L. between the North 1/4 corner and the center of Section 12.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- M-4 1" pine, 4" aluminum cap buried in road; N.E. corner of west bridge rail - S5°W - 79.4'; N.W. corner of east bridge rail - S9°E - 80.3'; 11" Maple - S14°E - 108.6'; 8" W. Ash - N81°W - 65.7'; Centerline N-S blacktop road - East - 3'.
- 3 1" pipe, 4" aluminum cap; 9" R. Pine - N25°E - 48.55'; 9" R. Pine - N9°W - 51.4'; 6" W. Pine - S26°E - 47.9'; 17" R. Pine - S27°W - 64.8'; Centerline R.R. Track - North - 16'.
- 5 3/4" pipe and plastic R.L.S. cap; 8" R. Pine - N1°E - 35.6'; 7" R. Pine - N48°W - 43.7'; 8" R. Pine - S5°W - 65.1'; 7" R. Pine - S26°E - 50.4'; D.N.R. witness monument - South - 50.00'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt DATE 6-26-80  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558