

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

..... <u>Marquette</u>	Located In:	Corner Code <u>11</u>
(County)		
1. Public Land Survey	T 47N R 23W	A-12, B-12, C-12.
	T R	
	T R	
	T R	
2. Property Controlling	S T R	
in Section	S T R	
3. Miscellaneous	S T R	
Property in Sec.	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Paul Bressette, in a field survey on 6/22, 1992, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-12. Quarter corner common to Sections 31 and 36. W. A. Burt, D.S. 1845. Set wood post. Maple 10, N55E, 24 L. Birch 14, N55W, 17L.
- B-12. Center quarter corner of Section 31. Not set in original survey, no evidence of subsequent establishment.
- C-12. Quarter corner common to Sections 31 and 32. A.D. Sullivan, DS 1852. Set wood post Hemlock 16, N55W, 10; Hemlock 17, S69E, 23.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-12. No evidence of OBts. Corner position reestablished mid-point and on line between the northwest and southwest corners of Section 31. Distance north to Chocolay River fits proportioned distance within 0.5'.
- B-12. Corner established at the intersection of the N-S and E-W quarter lines of Section 31. Corner falls approximately 307 ft. north of the centerline of an abandoned RR grade.
- C-12. No evidence found of hemlock BTs or subsequent reestablishment. Corner re-established mid-point and on line between the northeast and southeast corners of Section 31.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|------------------------------|---------------------------|-------------------------|
| A-12. DNR Monument | B-12. DNR Monument | C-12. DNR Monument |
| 6" r.maple, N47E, 21.75' | 8" cedar, N72E, 31.0' | 5" maple, N80E, 18.2' |
| 9" r.maple, S48E, 6.0' | 5" r. maple, S77E, 14.05' | 5" maple, S30E, 31.55' |
| 4" twin R.maple, S45W, 5.55' | 6" r.maple, S64W, 32.1' | 5" y.birch, S63W, 50.1' |
| 8" r.maple, N39W, 11.0' | 6" w.pine, N56W, 20.5' | 6" maple, N19W, 41.3' |

Signed by Paul R. Bressette Date 9-28-92
 Surveyor's Michigan License No. 37270

