

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Marquette

(County)

Located In:

Corner Code ##

- |                                    |   |     |   |     |             |
|------------------------------------|---|-----|---|-----|-------------|
| 1. Public Land Survey              | T | 47N | R | 23W | A-11, B-11. |
|                                    | T |     | R |     |             |
|                                    | T |     | R |     |             |
|                                    | T |     | R |     |             |
| 2. Property Controlling in Section | S | T   | R |     |             |
|                                    | S | T   | R |     |             |
| 3. Miscellaneous Property in Sec.  | S | T   | R |     |             |
|                                    | S | T   | R |     |             |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Paul Bressette, in a field survey on 5/12, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-11. Corner common to Sections 30, 31, 25, 36. W.A. Burt, D.S., 1845. Set wood post, Birch 16, N60E, 39 L; Hemlock 14, N49W, 48L. A.D. Sullivan, D.S., 1852. Hemlock 22, S37E, 53L, Birch 14, N62E, 35 L.

B-11. Quarter corner common to Sections 30 and 31. A.D. Sullivan, D.S. 1852. Set wood post, Cedar 9, S23W, 23 L; Birch 14, N62E, 35 L. W. Burt, Examiner of Surveys, 1854. Cedar 9, S17W, 24 L; Y. Birch 6, N30E, 18L.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11. Found 1" iron pipe, location poster and several trees with old blazes. Distance North to quarter corner set from original evidence 2650.87' (GLO 2640) and south to 1. bank Chocolay River 1729.49'. (GLO 1725.9'). Cedar stump for line tree found +50' south of riverbank and on line between found iron and iron set by RLS 17618. Distance to found iron to south 5288.57 (GLO 5280). Proportioned distances to found iron, riverbank and cedar stump fit almost exactly. Replaced iron pipe with DNR monument and witnessed. Corner falls 124' north of abandoned RR grade.

B-11. No evidence found of cedars or birch. Old Y. Birch stump found north of proportioned position, but badly rotted and no marks found. Corner position re-established by single proportion between the northeast and northwest corners of Section 31. Old squared hemlock ±8 ft. north of monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                          |                           |
|--------------------------|---------------------------|
| A-11. DNR Monument       | B-11. DNR Monument        |
| 6" w. spruce N19E, 39.7' | 5" red maple, N21E, 11.7' |
| 4" sugar, S12E, 5.0'     | 6" cedar, S02W, 27.9'     |
| 16" cedar, S34W, 51.5'   | 6" cedar, S73W, 14.9'     |
| 8" sugar, N54W, 7.35'    | 8" cedar, N55W, 25.6'     |



Signed by Paul R. Bressette

Date 9-28-92

Surveyor's Michigan License No. 37270