

1994 DEC 28 PM 5:56

JOB NUMBER: 94030
SHEET NO.: 1-483

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>23W</u> M-10	<u>A-10</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Patricia A. Morley
REGISTER OF DEEDS

LIBER 1 PAGE 154
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Tuesday, December 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10: East 1/4 Corner of Section 25, 1844; William A. Burt's monument at point of old stake. Referenced by: original survey notes describe the corner monument as a wood 5" Tamarack N31E, 18.2' 6" Tamarack S31E, 4.3' post referenced by: 6" Tamarack S83W, 8.25' 6" Tamarack N01W, 16.6' 9" Tamarack N28E, 14 L 12" Tamarack N47W, 65 L L. 5 R.C., Pg. 358.
1992: Land Corner Recordation Certificate recorded by Paul Bressette LLS No. 37270 indicates a found 1" iron pipe, Tamarack stub NE with axe marks and Tamarack stump NW in proper position for OBTs. Excavation at pipe revealed 3 stake points, one considerably older than others. Set DNR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted DNR monument as referenced by Paul Bressette, P.S. No. 37270 in Part A above. Distance North is 2643.30' and distance South is 2650.75'.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Henry J. Bussome
DATE 10/31/1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Found Department of Natural Resources iron pipe with 4" diameter aluminum cap in place referenced by nails in:
5" Tamarack N15W 16.96 ft. Bressette NBT
5" Tamarack N23E 18.28 ft. Bressette NBT
5" Tamarack S57E 21.47 ft.
4" Tamarack S50W 24.73 ft.
Steel sign post South 1.0 ft.
Monument is 1.0' East of a 3" diameter wood post. Stamped MCR 1994 on cap of monument (Marquette County Remonumentation).
Bk. 5, Pg. 113

Signed by Gerald W. Carlson Date 12-22-94
Surveyor's Michigan License No. 24589

