

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Marquette

(County)

Located In:

Corner Code #

1. Public Land Survey

T 47N R 25W      K7  
T    R                      \_\_\_\_\_  
T    R                      \_\_\_\_\_  
T    R                      \_\_\_\_\_

2. Property Controlling  
in Section

S    T    R                      \_\_\_\_\_  
S    T    R                      \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S    T    R                      \_\_\_\_\_  
S    T    R                      \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Jul 17 1996

I, Paul R. Bressette, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

(A) Description of original monument and accessories and/or subsequent restoration:  
(K7) Section corner common to Sections 13, 14, 23 and 24. 1852: A.D. Sullivan, DS. Set wood post witnessed by: Hemlock 12 N21E 16 lks.; Hemlock 12 S50W 29 lks. 1940's: Marquette County Road Commission. 1" iron pin, no witnesses. 1976: Michigan Dept. of Natural Resources, Dave Babbitt, RLS 21558. Replaced 3/4" iron pipe with DNR monument witnessed by: 6" W.Birch N86E 14.25'; 6" W.Pine S66E 28.00'; 6" W.Pine S13W 23.30'. 1993: Certified Survey in L.1 of Surveys, pps. 82-86 and pps. 101-106 by Dennis Destrampe, RLS 18983 shows 3" aluminum capped pipe (pps.82-86) and 1" iron pin (pps.101-106) witnessed by: 6" W.Birch N86E 14.25'; 6" W.Pine S66E 28.00'; 6" W.Pine S13W 23.30'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K7) Found DNR monument and 8" W.Birch witness S89E 14.15' from monument. The other witnesses fall in the newly cleared R/W of Co.Rd. 480. Lower face of Birch is rotted and the top is dead. Monument was re-witnessed as found, and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

(K7) Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR MONUMENT  
7" W.Pine N85E 29.8' (S13,NBT)  
9" W.Birch S60E 10.9' (S24,NBT)  
7" R.Maple S19W \*11.79' (S24,NBT)  
5" R.Maple N67W 33.65' (S14,NBT)  
All trees are blazed, scribed and painted. Measurements are to notch in butt blaze except "\*" which is to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette  
Surveyor's Michigan License No. 37270

Date 1-13-97

For the Michigan Department of Natural Resources - Forest Management Division