

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Marquette (County)
1. Public Land Survey T 47N R 25N K6
2. Property Controlling in Section S 14 T 47N R 25N 9
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Jul 02 1996

I, Paul R. Bressette, in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Cell (6, J) contains a dot representing a corner point.

A. Description of original monument and accessories and/or subsequent restoration:

(K6) Quarter corner common to Sections 13 and 14. 1852: A.D.Sullivan, DS. Set wood post witnessed by: Hemlock 12 S80E 41 lks.; Maple 6 N83W 12 lks. 1993: Certified Survey in L.1 of Surveys, pps.82-86 and pps.101-106 by Dennis DeStrampe, RLS 18983 shows found 1 1/4" iron pipe witnessed by: 12" Maple N84E 42.74'; 5" Maple S09W 38.61'; 7" W.Birch S88W 52.51'; 8" Maple N18W 15.43'. (9) East One-sixteenth corner of Section 14. 1993: A Certified Survey in L.1 of Surveys, pps.82-86 and pps.101-106 by Dennis DeStrampe, RLS 18983 shows set 1/2" rebar with plastic cap witnessed by: 7" Maple N02W 29.94'; 7" Maple N56E 33.61'; 5" Maple S57E 13.95'; 13" Twin Oak S78W 18.60'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K6) Found 1 1/4" iron pipe with plastic cap (RLS 24589) and witnesses as described. Iron pipe was replaced with DNR monument, driven below grade next to monument, and is accepted as the best available evidence of the position of the original corner. (9) Found capped rebar and witnesses as described. A closed traverse around the south half of Section 14 revealed a difference of 3.36 feet from the E 1/4 to the SE corner of Section 14, resulting in DeStrampes corner being 2.85 feet from its intended position. Rejected DeStrampes corner and set a DNR monument in the proper position and witnessed. Corner falls approximately 25 feet east of a trail road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K6) DNR monument 14" R.Maple N85E 42.69' (1/4S,NBT) 06" R.Maple S11W 38.56' (1/4S,NBT) 08" W.Birch N88W 52.47' (1/4S,NBT) 09" R.Maple N16W 15.36' (1/4S,NBT) All trees are existing NBT's and are blazed, scribed and painted. Measurements are to double headed nail w/ shiner, bearings are magnetic. (9) DNR monument 08" R.Maple N70E 34.51' (1/16S,BT) 06" R.Maple S52E 16.60' (1/16S,BT) 10" Twin Oak S77W 17.09' (1/16S,BT) 08" R.Maple N08E 28.01' (1/16S,BT) All trees are blazed, scribed and painted. Measurements are to double headed nail with shiner, bearings are magnetic.



Signed by Paul R. Bressette Date 1-13-97
Surveyor's Michigan License No. 37270

For the Michigan Department of Natural Resources - Forest Management Division