

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Marquette Located In: Corner Code #
1. Public Land Survey T 47N R 25W 16
2. Property Controlling in Section S 14 T 47N R 25W 8
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims
8 Jul 10 1996
16 Jun 24 1996

I, Paul R. Bressette, in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Cell (6, I) contains a dot representing a corner point.

A. Description of original monument and accessories and/or subsequent restoration:
(16) Quarter corner common to Sections 14 and 15. 1852: A.D. Sullivan, D.S. Set wood post witnessed by: Sugar 10 N39W 23 lks.; Sugar 12 N40E 54 lks. No date: William Donnan, RLS 17618. Notes show set, but do not mention type of monument, and witnessed by: 16" Maple S49E 11.20'; 12" Maple S73W 9.59'; 10" Y.Birch S12E 26.22'. 1992: A certified survey recorded in L.I of Surveys, pps. 82-86 and pps. 101-106 by Dennis DeStrampe, RLS 18983 shows corner mid-point and on-line between the Northwest and Southwest corners of S.14, not monumented.
(8) West One-sixteenth corner of Section 14. Not set in original survey, no evidence of-subsequent establishment. Found iron fence post about 80 feet south of monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(16) Found and rejected Donnan witnesses and hole in ground where monument had been. Examination of Donnan's notes, and conversation with former employee, reveal improper method of reestablishment. No evidence of original monument or BT's found. Corner position reestablished mid-point and on-line between the northwest and southwest corners of S.14. Distances to terrain calls north and south of corner position check fairly well.
(8) Corner position established mid-point and on-line between the Center and West Quarter corners of Section 14.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(16) DNR monument (8) 1" iron pipe w/4 aluminum cap
06" Sugar N35E 28.8' (1/4S,NBT) 04" Oak S27E 50.3' (1/16S,BT)
15" Sugar S65E 41.65' (1/4S,NBT) 04" W. Pine S46W 15.8' (1/16S,BT)
06" Y.Birch S58W 23.25' (1/4S,NBT) 10" R. Pine N55W 22.3' (1/16S,BT)
20" Oak N41W 6.8' (1/4S,NBT) 19" W. Pine N19W 36.1' (1/16S,BT)
All trees are blazed, scribed and painted. Measurements are to notch in butt blaze, bearings are magnetic.



Signed by Paul R. Bressette Date 1-13-97
Surveyor's Michigan License No. 37270

For the Michigan Department of Natural Resources - Forest Management Division