

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey
 T ___ R ___
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling
 In Section S 22 T 47N R 25W Ref 1/64 E of 8
 S 22 T 47N R 25W Ref 1/64 E of 11

3. Miscellaneous
 Property in Sec. S ___ T ___ R ___
 S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

Ref Jul 17 1996
 Ref Jul 24 1996

I, Paul R. Bressette, in a field survey on _____, 19__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (1/64 E of 8) One sixty-fourth corner between the West one-sixteenth corner and the Center Quarter corner of Section 22. Not set in original survey, no evidence of subsequent establishment.
 (1/64 E of 11) One-sixty-fourth corner between the Southwest and South one-sixteenth corners of Section 22. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (1/64 E of 8) Corner position established mid-point and on-line between the West one-sixteenth and Center Quarter corners of Section 22.
 (1/64 E of 11) Corner position established mid-point and on-line between the South and Southwest one-sixteenth corners of Section 22.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (1/64 E of 8) DNR monument
 5" R. Pine N35E 28.1' (1/64, BT)
 4" J. Pine S55E 26.05' (1/64, BT)
 8" W. Pine S12W 6.0' (1/64, BT)
 6" W. Pine N55W 13.05' (1/64, BT)
 All trees are blazed, scribed and painted. Measurements are made to notch in butt blaze, bearings are magnetic.

(1/64 E of 11) DNR monument
 12" J. Pine N12E 18.75' (1/64, BT)
 04" J. Pine S47E 11.2' (1/64, BT)
 05" J. Pine S58W 32.35' (1/64, BT)
 06" J. Pine N68W 17.85' (1/64, BT)
 All trees are blazed, scribed and painted. Measurements are made to notch in butt blaze, bearings are magnetic.



Signed by Paul R. Bressette Date 1-13-97
 Surveyor's Michigan License No. 37270

For the Michigan Department of Natural Resources - Forest Management Division