

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-345
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORDATION
1993 DEC 22 PM 4:15
Gerald W. Carlson
RECORDED BY

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
	1.	
1. Public Land Survey	T 48N R 25W	A-13
	T 48N R 26W	M-13
	T 47N R 25W	A-1 ✓
	T 47N R 26W	M-1
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Liber 1 R.C. Page 24
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Saturday, December 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-13: Section Corner common to Section 31, T48N-R25W; Section 6, T47N-R25W; Section 36, T48N-R26W; and Section 1, T47N-R26W. 1845: William A. Burt's original survey notes describe the corner as a wood post referenced by: 24" Hemlock N79W, 75 1 20" W.Pine S63E, 45 1	No date given - Cummings recorded survey indicates the SW corner of Section 31 verified by bearing trees. This distance North of this corner is listed at 2640, the distance East from this corner is listed at 2456.3. No date given - Marquette County Road Commission book indicates a pipe at corner of old fence. No corner accessories given. (See reverse side)
---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found a P-K set from George Wilson's witnesses. Chipped asphalt out and found 1 1/2" iron pipe 1.10 ft. below surface of asphalt. Also found cap for 5/8" iron buried next to pipe with RLS #17618. Set a 3/4" rebar 18" long inside 1 1/2" diameter pipe in Payne & Dolan road. Set a Marquette County Survey Monument on top of 3/4" rebar in monument box. Tablet is 0.6 below surface of road. Distance North is 4.73 ft. short of Cummings, distance East measures 2.45 ft. short of Cummings. Peer group ratification 11-29-93.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set 3/4" rebar 18" long inside 1 1/2" diameter pipe with Marquette County Survey Monument cap on top of 3/4" rebar stamped to identify the corner in a monument box in the black top of Payne & Dolan Road referenced by nails in:

8" Maple	N62E	94.20 ft.
9" Spruce	S33E	89.30 ft.
Power Pole	S53W	72.4 ft. Donnan witness
Power Pole	N88W	109.50 ft.

The power poles are the southeasterly poles of the Northwesterly two group of three poles of three groups of three poles at a PI in the power line. Monument is 0.6 ft. below surface of the road.
Bk. 3, Pg. 140

Signed by Gerald W. Carlson Date 12-22-93
Surveyor's Michigan License No. 24589



Record No. 345

Part "A" Continued:

1972 - William Donnan found a 1 1/4" iron pipe

5" Maple	N70°E	50.89 ft.
12" Tamarack	S75°E	59.67 ft.
Power Pole	S51°W	72.54 ft.

This corner not recorded.

1976 - George Wilson recorded a old iron pipe with iron rod inside with RLS cap 17618 that lines up with an old fence line running easterly from corner referenced by:

Face of a power pole	S65°W	82.90 ft.
Face of a power pole	S10°W	85.90 ft.

L1 RC, Pg. 143

Handwritten:
\$9,000
\$1,000
\$1,000