

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD 1995 DEC 27 AM 7:41

JOB NUMBER: 95053 SHEET NO. : 1-617

APR 01 1996 LAND CORNER RECORDATION CERTIFICATE COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE (County) Located In: Corner Code #

Patricia A. Mosley REGISTER OF DEEDS

Table with 3 columns: Description, Township/Range, and Corner Code. Includes entries for Public Land Survey, Property Controlling, and Miscellaneous Property in Section.

LIBER 1 PAGE 235

Register of Deeds Stamp & File Number

1. Lot No. , Recorded Plat Private Claims

Grid table with columns A-L and rows 2-13, containing numerical values for recording purposes.

GERALD W. CARLSON Wednesday, August 23 95

in a field survey on , 19 I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

M-2: Quarter Corner common to Section 1, T47N-R26W and Section 6, T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by: 24" Hemlock S82W, 13 1 15" Cedar N81E, 25 1 No Date: The corner is indicated on an easement map for Northern Natural Gas Company. No accessories given.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a Magic Marker "X" on rock as set single proportionally on line between the SE and NE Corners of Section 1 by Gerald W. Carlson in 1988. Distance North is 2457.25', and Distance South is 2627.93'.

RATIFIED BY PEER GROUP P.A. 345 OF 1990

Garry J. Bussone DATE 12/4/95

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Replaced found Magic Marker "X" with a 3/8" X 8" Rebar, drilled and grouted in rock, and capped with a 3 1/4" aluminum tablet Marquette County Survey Monument, 0.15' above surface, and stamped to identify the corner. Referenced by nails in existing G. Carlson Bearing Trees: 12" Cedar N38W, 21.66' (Carlson N.B.T.) 15" Cedar N53E, 15.22' (Carlson N.B.T.) 15" Hemlock S59E, 23.14' (Carlson N.B.T.) 15" Maple S04W, 17.04' (Carlson N.B.T.) Green Steel Sign Post w/Survey Marker Sign S46W, 1.83' Bk. 10, pp. 5-6.



Recorded by Gerald W. Carlson 24589

Date 12-15-95

Surveyor's Michigan License No.