

APR 01 1996

JOB NUMBER: 95053  
 SHEET NO. : 1-618

LAND CORNER RECORDATION CERTIFICATE  
 COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD  
 1995 DEC 27 AM 7:44

For corners in \_\_\_\_\_ Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 MARQUETTE (County)

*Patricia A. Moberg*  
 REGISTER OF DEEDS

1. Public Land Survey	T 47N	R 26W	M-3
	T 47N	R 25W	A-3
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Section	S	T	R
	S	T	R

LIBER 1 PAGE 236  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, GERALD W. CARLSON, in a field survey on Wednesday, August 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-3: Section Corner common to Sections 1 and 12, T47N-R26W 18" Y. Birch S43W, 33.6' and Sections 6 and 7, T47N-R25W. 1844: William A. Burt's 1947: MCRC notes from F.B. 601, pp. 152-153, indicate that original survey notes describe the corner monument as a wood old B.T., 20" Sugar S82W, 18 L, is still standing and post referenced by:  
 20" Sugar S82W, 18 L and Balsam post in mound of stones. Set reference:  
 12" Sugar N33E, 20 l 30" Y. Birch S60E, 11.5'; Found references:  
 No Date: MCRC notes from F.B. 517 (No pg. # - 3/4 into book) Y. Birch Stump S42W, 33.6'  
 indicate the corner as a set 3/4" circular iron pin. Called Sugar Stump S08E, 30.1'  
 old B.T.'s good, but did not list them. Set new B.T.'s: 1965: The corner is indicated on an unrecorded Upper Peninsula Power Company R.O.W. map. (See Reverse Side).  
 12" Maple Stump S06E, 30.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a 1" iron pipe, bent over, as previously found by G. Carlson in 1988. Distance South is 5254.76', and Distance North is 2627.93'.

RATIFIED BY PEER GROUP  
 P.A. 345 OF 1990

*Larry J. Bussard*  
 DATE 11/6/95



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Replaced found iron pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" aluminum tablet Marquette County Survey Monument, flush with ground, and stamped to identify the corner. Referenced by aluminum nails set in:

11" S. Maple	N30E,	16.74'
8" S. Maple	N74E,	27.27'
7" S. Maple	S40E,	12.90'
6" B. Cherry	N66W,	19.79'
Green Steel Sign Post w/Survey Marker Sign	S39W,	1.75'

Note: Monument leans slightly East due to large rock below the surface. Corner is +/- 175' North of C/L of old Co. Rd. 480.

Bk. 10, pp. 1-4.

Signed by Gerald W. Carlson

Date 12-15-95

Surveyor's Michigan License No. 24589

**Record NO. 618:**

**Part A Continued:**

No Date: The corner is shown on an easement map for Northern Natural Gas Company recorded in L. 72, MR Pg. 585.

No Date: The corner is indicated on an easement map recorded in L. 289, Deeds Pg. 186.

No Date: The corner is indicated on an easement map recorded in L. 290, Deeds Pg. 224.

No Date: The corner is indicated on an easement map recorded in L. 290, Deeds Pg. 272.

1976: An LCRC recorded by George B. Wilson RLS #17607, in L. 1, RC Pg. 141, indicates the corner as a found 16" X 10" quartz stone, rectangular on top, nested in a group of stones. Bearing trees notched facing corner. Iron pipe lying horiz. on top of ground next to stone. No other evidence found. Established references:

10" Maple	N28E,	16.4'
8" Maple	S38E,	12.3'

1989: The corner is indicated on an Easement Description Map for Wisconsin Electric recorded by Sundberg, Carlson, and Associates in L. 130, MR Pg. 755. No accessories given.

*Handwritten:*  
J.H.  
Geo. B. Wilson