

APR 01 1996

1995 DEC 27 AM 7:44

JOB NUMBER: 95053
SHEET NO.: 1-622

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____ Located In: _____ Corner Code # _____

_____ (County)

1. Public Land Survey T 47N R 26W M-7
T 47N R 25W A-7 ✓
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

Patricia L. Moberg
REGISTER OF DEEDS

LIBER 1 PAGE 240

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

GERALD W. CARLSON, in a field survey on Wednesday, November 8, 1995, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found or expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

M-7: Section Corner common to Sections 13 and 24, T47N-R26W established by proportionate measurement. Referenced by: and Sections 18 and 19, T47N-R25W. 1844: William A. Burt's 8" J. Pine N76W, 32.34' original survey notes describe the corner monument as a wood 10" W. Birch N56E, 23.75' post referenced by: 1951: MCRC P.B. #651 indicates the corner and references as recorded above in Record of Surveys Book #1, Pg. 131. 1989: The corner is indicated on an Easement Description Map for Wisconsin Electric recorded by Sundberg, Carlson, and Associates in L. 130, MR Pg. 756. 1951: The corner is indicated as a 1" pipe with 4" Brass Cap on a Land Corner Record in Record of Surveys Book #1, Pg. 131, recorded by Michigan Department of Conservation Forestry Division (Dean C. De La Mater, RLS #05778). Corner was

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a 1 1/4" dia. galvanized pipe, 1.0' above ground, with a 4" dia. Michigan Department of Conservation brass cap, stamped to identify the corner. Monument is 12' +/- East of a two-track Rd.. Distance North is 5254.01', and Distance South is 2616.93'.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990
Larry J. Bussone
DATE 11/6/95

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Rewitnessed existing Michigan Department of Conservation Monument using double headed nails set in:

14" Spruce	N13W,	56.57'
13" W. Pine	N54E,	33.83'
16" W. Pine	N79E,	68.42'
12" J. Pine	S52E,	24.34'
Green Steel Sign Post w/Yellow Survey Marker Sign	North,	2.0'

Note: Bearing Trees were face and butt blazed, painted, and had bearing tree tags affixed.
Bk. 9, pp. 57-58.



Signed by *Gerald W. Carlson*

Date 12-15-95

Surveyor's Michigan License No. 24589