

JOB NUMBER: 95053
SHEET NO.: 1-625

APR 01 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
MARQUETTE COUNTY
1995 DEC 21 AM 11:45
RECEIVED FOR RECORD

For corners in

MARQUETTE (County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|--------------|--------------|---------|
| 1. Public Land Survey | T <u>47N</u> | R <u>26W</u> | M-10 |
| | T <u>47N</u> | R <u>25W</u> | A-10 ✓ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous | S _____ | T _____ | R _____ |
| Property in Section | S _____ | T _____ | R _____ |

1995 DEC 21 AM 11:45
REGISTER OF DEEDS
Patricia A. Menley
REGISTER OF DEEDS

LIBER 1 PAGE 243

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Tuesday, November 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10: Quarter Corner common to Section 25, T47N-R26W and Section 30, T47N-R25W, 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
4" S. Pine S15E, 10 l
3" S. Pine N36W, 5 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Searched, and no subsequent evidence or corner was found. Corner position established by single proportion measurement on line between the S.E. and N.E. Corners of Section 25. Distance North is 2654.27', and Distance South is 2654.27'.

RATIFIED BY PEER GROUP
P.A. 445 OF 1990

Harry J. Bussone
DATE 11/6/95



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument, 2" above ground, and stamped to identify the corner. Referenced by double headed nails set in:
7" J. Pine S41W, 36.41'
8" J. Pine N64W, 36.17'
7" J. Pine N40E, 48.75'
5" J. Pine N79E, 31.57'
Green Steel Sign Post w/Yellow Survey Marker Sign West, 1.0'
Note: Bearing trees were face and butt blazed, painted, and had bearing tree tags affixed. Corner falls 50.7' West of C/L of 2-track road.
Bk. 9, pp. 69-70.

Signed by *Gerald W. Carlson* Date 12-15-95
Surveyor's Michigan License No. 24589