

SURVEY & REMONUMENTATION

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

JOB NUMBER: 94030
SHEET NO. : 1-431

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 5:54

For corners in

COMMISSION

MARQUETTE <small>(County)</small>	Located In:	Corner Code <u>44</u>	
1. Public Land Survey	T <u>47N</u> R <u>25W</u>	C-1	
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

Patricia L. Monley
REGISTER OF DEEDS

LIBER 1 PAGE 106
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Tuesday, November 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<p>C-1: Section Corner, to Sections 5 and 6.</p> <p>1845: A.D. Sullivans original survey notes describe the Corner Monument as a wooden post 40 I West of the Section Corner, to Sections 31 and 32, T48N-R25W.</p> <p>Referenced by:</p> <p>14" Birch S39E, 30 l</p> <p>8" Sugar S10W, 18 l</p>	<p>1988 - G. Carlson set a 5/8 by 18" iron and RLS Cap No. 24589 26.40' (40 l) West of the re-established Corner to Sections 31 and 32, T48N-R25W and on line between the Southeast Corner of Section 31 and South 1/4 Corner of Section 31, T48N-R25W.</p> <p>Referenced by:</p> <p>8" Maple S52W, 8.25'</p> <p>12" Maple N54W, 16.79'</p> <p>16" Maple N22W, 28.59'</p> <p>18" Maple N62E, 15.59'</p> <p>This Corner was not recorded.</p>
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 - Found and accepted the iron as placed by G. Carlson in 1988.
Distance West is 2629.71' and distance East is 2658.07'.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990
Luoy J. Bassine
DATE Oct. 3, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Replaced 5/8" iron and cap #24589 with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

9" Maple S45W 8.16 ft. Carlson NBT

12" Maple N59W 16.75 ft. Carlson NBT

17" Maple N26W 28.57 ft. Carlson NBT

18" Maple N60E 15.67 ft. Carlson NBT

Steel sign post East 1.0 ft.

Monument is 0.40' above ground.

Bk. 5, Pg. 59



Signed by Gerald W. Carlson Date 12-22-94

Surveyor's Michigan License No. 24589