

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1999 DEC 22 AM 11:26

Patricia A. Mosley
REGISTER OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 47N R 25W _____ C-13
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER **R2** PAGE **217**

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on November 4th, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
C-13: Corner common to Sections 31 and 32, T47N-R25W on the South Township line, 1844: William A. Burt's original township boundary survey notes describe the corner monument as a wood post referenced by:
6" Spruce Pine N75E, 12L 5" Spruce Pine N17W, 11L

1986: A survey calculation sheet by Gerry Carlson, P.S. #24589, indicates the corner location distance N89-56-19W, 2635.77' to an existing monument at the South quarter corner of Section 31, distance S89-56-19E, 5271.54' to a DNR monument at the section corner common to Sections 32 and 33, and distance N00-11-23W, 5309.92' to an iron pin at the section corner common to Sections 29, 30, 31, and 32, T47N-R25W.

1986: A section breakdown calculation sheet by Gerry Carlson, P.S. #24589, indicates the corner location with the same information as above.

1990: An easement map by Sundberg, Carlson and Associates, Inc., indicates a corner. No description or accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-13: 1999: No original corner evidence found. Corner position established by single proportionate measurement on a latitudinal curve between the Southwest corner of Section 31 and the Southeast corner of Section 32, T47N-R25W. Distances are 2636.31' West and 2636.30' East along the South Township Line of T47N-R25W to the South quarter corners of Sections 31 and 32. The Northeast corner of Section 6, T46N-R25W is West 23.76'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-13: 1999: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.10' above ground. Referenced by:
9" Jack Pine NO2E, 57.94' 9" Jack Pine S42E, 36.53'
9" Jack Pine S02W, 71.88' 6" Jack Pine S20W, 52.83'
N.E. Corner Section 6 (cc) N90W, 23.76'

Green Steel Sign Post w/ Yellow Survey Marker Sign S05W, 3.04'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.
Bk. 12, Pg. 94 T46N-R25W Corner Search Sheet 99100
Bk. 12, Pg. 140-141

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Buswell
DATE 11/1/99



Signed by Gerald W. Carlson Date 12-2-99

Surveyor's Michigan License No. 24589