

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 28 PM 5:54

Patricia A. Mosley
REGISTER OF DEEDS

JOB NUMBER: 94030

SHEET NO. : 1-433

For corners in

	MARQUETTE (County)	Located In:	Corner Code ##
1. Public Land Survey		T 47N R 25W	D-1
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

LIBER 1 PAGE 108
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, November 30, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 D-1: North Quarter Corner Section 5, T47N-R25W. Not part of original survey.
 1988: G. Carlson set 5/8" x 18" re-bar w/LLs cap equidistant between NW and NE Corners of Section 5 on-line between SW and SE Corners of Section 32, T48N-R25W. Referenced by:
 7" Y. Birch N85E, 49.31'
 10" Maple S35E, 25.54'
 10" Maple N81W, 12.30'
 8" Maple N07E, 16.22'
 This corner not recorded.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994 - Found and accepted iron as set by G. Carlson in 1988.
 Distance West is 2658.07' and distance East is 2657.68'.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**
Larry J. Basson
 DATE Oct. 3, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1994 - Replaced 5/8" iron and cap #24589 with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
 10" Yellow Birch N85E 49.36 ft. Carlson NET
 12" Maple N84W 12.28 ft. Carlson NET
 10" Maple N03E 16.17 ft. Carlson NET
 12" Maple S33E 25.55 ft. Carlson NET
 Steel sign post West 1.0 ft.
 Monument is 0.30' above ground.
 Bk. 5, Pg. 63



Signed by Gerald W. Carlson Date 12-22-94
 Surveyor's Michigan License No. 24589