

**SURVEY &  
REMONUMENTATION**

JOB NUMBER: 94030

SHEET NO. : 1-435

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1994 DEC 28 PM 5:54

For corners in  
MARQUETTE

**COMMISSION**

*Patricia L. Manley*  
REGISTER OF DEEDS

(County)	Located In:	Corner Code #
	47N 25W	E-1
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PAGE 110  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

GERALD W. CARLSON Wednesday, November 30 94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
E-1: Section Corner common to sections 4 and 5, T47N-R25W. 1988: G. Carlson set a 5/8" re-bar w/LLs cap 19.80' (30L)  
1845: A.D. Sullivan's original survey notes describe the west of the re-established SE Corner of Section 32, corner monument as a wood post set 30 l West of the Section T48N-R25W on line between the SE Corner and S 1/4 Corner Corner common to Sections 32 and 33, T48N-R25W, and of Section 32.  
referenced by:  
7" Birch S08E, 38 l  
8" Maple S27W, 35 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1994 - Found and accepted iron as placed by G. Carlson in 1988.  
Distance West is 2657.69' and distance East is 2597.27'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1994 - Replaced 5/8" iron and cap #24589 with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
11" Maple N23E 21.82 ft. Carlson NBT  
8" Maple S47E 14.95 ft. Carlson NBT  
12" Maple S10E 12.89 ft. Carlson NBT  
12" Maple S07W 6.68 ft. Carlson NBT  
Steel sign post East 1.0 ft.  
Monument is 0.30' above ground.  
Bk. 5, Pg. 69

REVIEWED BY PEER GROUP  
P.A. 345 OF 1990

*Larry J. Bussone*  
DATE Oct. 3, 1994



Signed by *Gerald W. Carlson*  
24589

Date 12-22-94

Surveyor's Michigan License No. \_\_\_\_\_