

1999 DEC 22 AM 11: 27

Patricia A. Manley
REGISTER OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 47N R 25W _____ E-13
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER **R2** PAGE **219**
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on November 9th, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-13: Corner common to Sections 32 and 33, T47N-R25W on the South Township line. 1844: William A. Burt's original township boundary survey notes describe the corner monument as a wood post referenced by:
9" S. Pine N75E, 18L 12" S. Pine N55W, 17L

1953: A Land Corner Record by Dean Delameter, P.S. #5778 of the Michigan Department of Conservation, indicates a 1" pipe with a 4" brass cap with one reference:
4" J. Pine N67E, 12 links

Delameter states: "This corner was established by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this area. North to Summit of hill, West to rock knob, South to original B.T.'s. Corner was placed and witnessed September 18, 1952.

1986: Survey notes by Sundberg, Carlson and Associates, Inc., indicate a monument (no description) with the following references:
5" Maple in clump S36W, 13.52' 7" Double White Birch S85W, 78.9'
4" Maple in clump N03W, 122.9' 14" J. Pine N73E, 8.18' (Dept. Of Conservation B.T.)
w/scribe and blaze

Corner is located on slope 234.6' N. to rim, 180' W. to Rim.

1986: A section breakdown sheet by Sundberg, Carlson and Associates, Inc., indicates the corner distance N89-56-19W, 5271.54' to the Southwest corner and distance N00-02-41W, 2655.83' to the East quarter corner of Section 32.

1990: A section breakdown sheet by Sundberg, Carlson and Associates, Inc., indicates the corner distance N89-35-27W, 5264.67' to the Southeast corner of Section 33.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13: 1999: No original corner evidence found. Found and accepted a 1 1/4" outside diameter iron pipe painted orange with a 4" brass cap projecting 1.5' above ground. Distance West is 2636.30', East is 2631.97'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13: 1999: Stamped the accepted 4" brass cap on the 1 1/4" iron pipe with MCR 1999 which projects 1.5' above ground. Three existing references were measured:

14" Jack Pine N76E, 7.96' to set double headed nail (Dept. of Conservation 1953 NBT)
9" Twin Birch S86E, 79.77' to set double headed nail (SCA-1986 NBT)
6" Maple cluster N03W, 122.84' to set double headed nail (SCA-1986 NBT)

New reference established:
8" J. pine S58E, 58.73'

Green Steel Sign Post w/ Yellow Survey Marker Sign S12W, 2.6'
Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk.12, Pg.92 T46N-R25W Corner Search Report 99100

Signed by Gerald W. Carlson Date 12-8-99

Surveyor's Michigan License No. 24589

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Leary J. Bussone
DATE 11/1/99

