

**SURVEY &
REMONUMENTATION**

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

JOB NUMBER: 94030

SHEET NO. : 1-437

LAND CORNER RECORDATION CERTIFICATE

APR 28 1995 Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 5:54

For corners in

COMMISSION

MARQUETTE
(County)

Located In:

Corner Code ##

Patricia A. Monley
REGISTER OF DEEDS

1. Public Land Survey	T 47N	R 25W	F-1
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

LIBER 1 PAGE 112
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Tuesday, December 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1: North Quarter Corner Section 4, T47N-R25W. Not part of original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Corner position established equidistant between the NE and NW Corners of Section 4 on line between the S 1/4 Corner and SW Corner of Section 33. Distances East and West are 2597.27'. South 1/4 Corner Section 33, T48N-R25W is East, 17.16'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
 8" Maple N60E 4.95 ft. (cluster of 4 trees)
 7" Maple S40E 9.94 ft. (cluster of 4 trees)
 5" Maple S05W 20.67 ft.
 6" Maple S69W 15.77 ft. (cluster of 5 trees)
 Steel sign post North 1.0 ft.
 Monument is 0.2' above ground and located on steep side slope of North-South ridge.
 Bk. 8, Pg. 81

**VALIDATED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Bussard
DATE 9/3/1994



Signed by Gerald W. Carlson

Date 12-28-94

Surveyor's Michigan License No. 24589