

1999 DEC 22 AM 11:27

*Patricia A. Manley*  
REGISTER OF DEEDS *pm*

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 47N R 25W \_\_\_\_\_ F-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

LIBER **R2** PAGE **220**  
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on November 9th, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13: South Quarter Corner to Section 33, T47N-R25W.  
1844: William A. Burt's original township boundary survey notes describe the corner monument as a wood post referenced by:  
5" S. Pine N73E, 8L 5" S. Pine N11W, 5L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13: 1999: No original corner evidence found. Corner position established by single proportionate measurement on line between the Southwest and Southeast corners of Section 33, T47N-R25W. Distances are 2631.97' West and 2631.97' East along the South Township Line of T47N-R25W to the Southwest and Southeast corners of Section 33. The North quarter corner of Section 4 is West 27.06'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13: 1999: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.10' above ground. Referenced by:  
12" Twin Oak S46E, 18.08' 11" Twin Oak N27W, 67.60'  
14" Jack Pine S54W, 75.39' 8" Jack Pine S10W, 28.25'  
N 1/4 Section 4 46-25 (cc) N89W, 27.06'

Green Steel Sign Post w/ Yellow Survey Marker Sign S08W, 2.6'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. 12, Pg. 90 T46N-R25W Corner Search Sheet 99100

Bk. 12, Pg. 144

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990

*Larry J. Brunson*  
DATE 11/1/99



Signed by Gerald W. Carlson Date 12-8-99

Surveyor's Michigan License No. 24589