

1999 DEC 22 AM 11: 27

*Patricia R. Manley*  
REGISTER OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE

(County)

Located In:

Corner Code #

1. Public Land Survey      T 47N R 25W      G-13  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.        S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

LIBER **R2** PAGE **221**

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on October, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

**G-13:** Corner common to Sections 33 and 34, T47N-R25W on the South Township line.

1844: William A. Burt's original township boundary survey notes describe the corner monument as a wood post referenced by:

7" S. Pine      N47E,      15L      7" Aspen      N74W,      36L

(SEE REVERSE SIDE)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**G-13: 1999:** No original corner evidence found. Found and accepted a 4" brass tablet on a 1 1/4" iron pipe projecting 1.2' above ground.

Measured existing references:

10" Jack Pine (dead and fallen)      N18E,      29.2' to center (Buckler NBT)

Checked Line Call: West, 7.50 chains, top of hill (495'), with hip chain we measured 473'

Distance West is 2631.97', East is 2637.24'.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**G-13: 1999:** The monument is a 4" brass tablet mounted on a 1 1/4" iron pipe protruding 1.2' above ground. We stamped the existing monument with "MCR 1999" and established new references:

8" White Birch      S24W,      18.08'

6" White Birch      S86E,      19.45'

12" Spruce      S32E,      102.33'

Measured Existing references:

10" White Birch      N85W,      13.73' (Buckler NBT-1960)

9" Aspen      S48E,      10.10' to found nail (Buckler NBT-1960)

Green Steel Sign Post w/ Yellow Survey Marker Sign      N12E,      3.05'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. 12, Pg. 88

T46N-R25W

Corner Search Sheet

99100

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**RATIFIED BY PEER GROUP  
P.A. 345 OF 1990**

*Larry J. Benson*  
DATE 11/1/99



Signed by Gerald W. Carlson

Date 12-8-99

Surveyor's Michigan License No. 24589

**G-13:**  
**PART A CONTINUED:**

1959: A Land Corner Record by Billy Buckler, P.S. #08887, indicates a 1" pipe with a 4" brass cap with the following references:  
10" J. Pine (S 34 NBT) N20E, 44 L 5" White Birch (S 33 NBT) N86W, 21L  
7" Aspen (S 3 NBT) S50E, 15L

Billy States: " This corner was replaced at an old wood stake. Stake appears to be in line with E-W road 1/4 mile to the East. No evidence of original corner. Corner was placed and witnessed July 14, 1959."

1984: A section breakdown sheet by Gerry Carlson, P.S.# 24589, indicates the corner distance N89-32-15W, 5274.27' to the Southeast corner and distance N00-09-06E, 5351.53' to the Northwest corner of Section 34.

1986: Sundberg, Carlson and Associates, Inc. survey notes, indicate a corner (no description of the monument) with the following found references:

10" W. Birch	N63E,	6.32'
8" Aspen	S47E,	10.13' (Dept. of Conservation NBT)
8" Birch	N82W,	13.80' (Dept. of Conservation NBT)
9" J. Pine	N20E,	29.25' (Dept. of Conservation NBT)

1990: A section breakdown sheet by Gerry Carlson, P.S. # 24589, indicates the corner distance S89-35-27W, 5264.67' to the Southwest corner of Section 33.

SECTION