

**SURVEY &  
REMONUMENTATION**

JOB NUMBER: 94030  
SHEET NO. : 1-441

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

APR 28 1995

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
1994 DEC 29 AM 10:55

For corners in  
MARQUETTE  
(County)

**COMMISSION**

Located In:

Corner Code ##

	47N	25W	H-1
1. Public Land Survey	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

*Patricia A. Monahan*  
REGISTER OF DEEDS

LIBER 1 PAGE 114  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

GERALD W. CARLSON

Wednesday, December 28 94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
H-1: North Quarter Corner Section 3, T47N-R25W. Not part of original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1994: Corner position established equidistant between the NW and NE Corners of Section 3 on line between the SW and S 1/4 Corners of Section 34. Distances West and East are 2633.02'. The South 1/4 Corner of Section 34, T48N-R25W is East, 3.58'.

**RATIFIED BY PEER GROUP  
P.A. 345 OF 1990**

*Harry J. Bussone*  
DATE Oct. 3, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1994 - Set a 3/4" diameter rebar capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 11" Maple S51E 22.84 ft.
- 8" Maple S55W 21.48 ft.
- 26" Hemlock N30E 34.10 ft.
- 13" Twin Maple N12W 32.40 ft.
- Steel sign post North 1.9 ft.
- Monument is 0.2' above ground and grouted into rock on North slope of hill.
- Bk. 8, Pg. 87



Signed by *Gerald W. Carlson*  
24589

Date 12-29-94

Surveyor's Michigan License No. \_\_\_\_\_