

# SURVEY & REMONUMENTATION

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

JOB NUMBER: 94030  
SHEET NO. : 1-446

APR 28 1995

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 29 AM 10:56

For corners in

	<b>COMMISSION</b>	Located In:	Corner Code ##
	MARQUETTE <small>(County)</small>		
1. Public Land Survey	T <u>47N</u> R <u>25W</u>		<u>J-1</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____

*Patricia L. Monahan*  
REGISTER OF DEEDS

LIBER **1** PAGE **119**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, December 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

J-1: North Quarter Corner Section 2, T47N-R25W. Not part of original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994: Corner position established equidistant between the NW and NE Corners of Section 2 on line between the S 1/4 and the SE Corners of Section 35. The Corner falls 2.59' East of the South 1/4 Corner of Section 35 and the distances East and West are 2623.27'.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 8" White Birch N39E 59.42 ft.
- 6" Maple S21E 25.08 ft.
- 6" Maple S55W 54.88 ft.
- 6" Maple N78W 14.78 ft.
- Steel sign post South 1.5 ft.
- Monument is 0.20' above ground.
- Bk. 8, Pg. 97

**RATIFIED BY PEER GROUP**  
**P.A. 345 OF 1990**  
*Henry J. Busson*  
DATE Oct. 3, 1994

Signed by Gerald W. Carlson Date 12-29-94

Surveyor's Michigan License No. 24589

