

# SURVEY & REMONUMENTATION

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

JOB NUMBER: 94030  
SHEET NO. : 1-448

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 5:54

For corners in **COMMISSION**

*Patricia R. Manley*  
REGISTER OF DEEDS

MARQUETTE <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 47N R 25W	L-1 ✓
	T 48N R 25W	L-13
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PAGE 121  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Thursday, December 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

L-13: Quarter Corner common to Section 36, T48N-R25W and Section 1, T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:  20" Hemlock N35E, 45 l 24" Hemlock N62W, 17 l	1880: George P. Cummings survey indicates an iron at the corner with the following distances noted: West, 2623.50' and East, 2623.50'. No corner accessories given.  1910: Charles Cummings survey indicates a Corner for commencing a survey in Section 1, T47N-R25W. No corner accessories given. (See Reverse Side).
---	---

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994: Found and accepted DNR monument as referenced by G. Carlson in 1977. Distance West is 2623.41' and distance East to a calculated Township Corner in Lake Superior is 2632.61'.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1994 - Found Department of Natural Resources iron pipe with aluminum cap in place referenced by nails in:

7" Hemlock	S62E	23.31 ft.	Carlson NBT
11" Maple	S16W	8.24 ft.	Carlson NBT
8" Maple	N23W	43.01 ft.	Carlson NBT
15" Yellow Birch	N20E	33.89 ft.	Carlson NBT

Steel sign post South 1.35 ft.  
Monument is stamped MCR 1994 on cap (Marquette County Remonumentation).  
Bk. 5, Pg. 141

**RATIFIED BY PEER GROUP**  
**P.A. 345 OF 1990**

*Larry J. Bussone*  
DATE Oct. 3, 1994

Signed by Gerald W. Carlson

Date 12-28-94

Surveyor's Michigan License No. 24589



Record No. 448:

*Sub. 644  
P. 900  
P. 900*

Part "A" Continued:

1977 - G. Carlson indicates a pipe with an aluminum conservation department cap stamped to identify the corner referenced by:

(MDOT)	10" Maple,	S20W,	8.25'
	2" Maple,	N75W,	16.76'
	3" Poplar,	North,	26.55'
(Carlson)	5" Cedar,	S62E,	28.31'
	10" Maple,	S16W,	8.37'
	4" Maple,	N62W,	26.53'
	P.P.,	N75E,	32.36'
	LIRC, Pg. 329		

1982 - Corner indicated on MDOT R/W map Pages 24 & 25 - no corner accessories given.