

NEW REGISTRATION

MAR 12 1999

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1998 DEC 29 PM 3:23

For corners in

MARQUETTE

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 47N R 25W L-7
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Patricia L. Monberg
REGISTER OF DEEDS

LIBER **R 2** PAGE **125**

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on _____, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-7: Quarter Corner common to Sections 13 and 24.

1845: A.D. Sullivan's original subdivision survey notes describe the corner monument as a wood post referenced by:

8" Fir N89E, 18 L 6" Birch S48W, 11 L

1942: Survey field notes by Heilala from MCRC F.B. #628, Pg. 31, indicate the corner as being in C/L of Co Rd. 480. Distance East, 2649.9' to the S.E. Corner of section 13. No description of corner object or accessories given.

No Date: MCRC Government Corner Index Book #651 for Section 13 indicates the corner as a 1/2" X 18" rerod with RLS Cap #20711 in monument box referenced by:

U. Pole S07W, 52.26' (nail in W. side) 12" J. Pine N02W, 62.67' (60d spike W. side)
12" Maple S43W, 97.48' (nail in W. side) 14" W. Pine N37W, 80.87' (nail E. side)

No Date: A Certificate of Survey recorded in L. 144, MR Pg. 801 by Robert Cambensy, PS No. 19616 indicates the corner as being at C/L of Co Rd. 480. Distance S89-09'-51"E, 2640.57' to the N.E. Corner of Section 24. No description of corner object or accessories given.

1976: a Retracement Survey Map by Dave Babbitt, DNR Surveyor indicates a found pipe 56.6' North of a straight line between section corners 2643.2' West of NE Cor. Sec. 24. Babbitt apparently did not accept this iron pipe as he indicates no 1/4 corner found or established in his survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7: 1998: No original corner evidence found. The corner was set equidistant and on line between the SW and SE corners of Section 13 Distances East is 2640.66' and West is 2640.85'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7: 1998: Found a 1/2" rebar with RLS cap frozen in road in a monument box in the C/L of County Road 480. References by:


U. Pole S07W, 52.26' (nail in W. side) 12" J. Pine N02W, 62.67' (60d spike W. side)
12" Maple S43W, 97.48' (nail in W. side) 14" W. Pine N37W, 80.87' (nail E. side)

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails.

Bk. 14, Pg. 127

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
DATE 12/21/98



Signed by Gerald W. Carlson

Date 12-28-98

Surveyor's Michigan License No. 24589