

JOB NUMBER: 93300
SHEET NO. : 1-348
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Located In: MARQUETTE (County)

Corner Code #/

1. Public Land Survey	T <u>47N</u> R <u>24W</u>	<u>A-3</u>
	T <u>47N</u> R <u>25W</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1993 DEC 29 AM 10:39
MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD
REGISTER OF DEEDS
1 PAGE 50
LIBER Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Wednesday, December 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-3: Section Corner common to Sections 6 and 7, T47N-R24W and Sections 1 and 12, T47N-R25W, 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
12" Aspen S54E, 61
12" W.Birch N75W, 231

1975 - William R. Donnan, P.S. found a 1 1/4 inch iron pipe and reset a concrete monument at the corner.
Referenced by:
6" White Birch N50W 21.70 ft.
6" Maple N35E 16.02 ft.
6" Jackpine N80E 7.68 ft.

The corner is also shown on the recorded plat of Scenic Hills Estates. No corner accessories given.
L1 RC, Pg. 198

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 4" square concrete monument as set by William Donnan in 1975. Accepted this found concrete monument as the corner and set a Marquette County Survey Monument at the corner position.
No original G.L.O. evidence found. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced concrete monument with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
7" Maple S06E 25.94 ft.
8" White Birch N49W 21.72 ft. Donnan NBT
8" Jack Pine N33E 7.70 ft.
8" Jack Pine N70E 3.12 ft.
Monument is 0.4 ft. above ground.
Bk. 4, Pg. 8



Signed by Gerald W. Carlson Date 12-23-93
Surveyor's Michigan License No. 24589